COMMISSIONER MEETINGS
All meetings take place in the Commissioners Conference Room (308)
located in the Ostlund Building @ 2825 3rd Ave N (3rd Floor)
and are open to the public unless otherwise noted

THURSDAY - NOVEMBER 5, 2026

8:45 Calendar

9:00 COMMISSIONERS DISCUSSION

PLEDGE

DEPARTMENTS

1. **MetraPark -** Additional AED's for MetraPark
2. **Finance -**
   a. Sletten-Courthouse Renovation Judge's Recommendations
   b. Sletten-Courthouse Renovation Flooring Carpet vs. L.V.T.

COMMISSIONERS

1. Board Recommendation - Michael Temporal to Allies in Aging
2. Commissioner Board Reports

PUBLIC COMMENTS ON COUNTY BUSINESS

**Public comment is an opportunity for individuals to address the Board, however, the Board cannot engage in discussion or take action on items not properly noticed on the agenda. Public comment is limited to 3 minutes per individual.*

B.O.C.C Thursday Discussion 1.

Meeting Date: 11/05/2026

Title: Metrapark AED's

Submitted By: Teri Reitz, Board Clerk

TOPIC:

MetraPark - Additional AED's for MetraPark

BACKGROUND:

N/A

RECOMMENDED ACTION:

Discuss.

B.O.C.C Thursday Discussion 2. a.

Meeting Date: 11/05/2026

Title: Sletten-Courthouse Renovation Judge's Recommendations

Submitted By: Jared Gavin

TOPIC:

Sletten-Courthouse Renovation Judge's Recommendations

BACKGROUND:

Sletten is requesting approval from the Yellowstone County Commissioners on Judge's Recommendations for Courthouse Renovation. The total for all selections is $164,034.17.

RECOMMENDED ACTION:

Approve and return a copy to finance.

Attachments


A&E Design Arch Bulletin

Courthouse Renovation-Judge's Itemized Requests

ROM Judge Walk Summary

MEZZANINE DEMOLITION LEGEND

- DENOTES APPROXIMATE LOCATION OF TEMPORARY SHORING JACK - TO BE INSTALLED PRIOR TO DEMOLITION
- DENOTES EXTENTS OF EXISTING MEZZANINE FLOOR DEMOLITION - REMOVED 2ND
- DENOTES 1ST CUT LINE - CUT NORTH AND SLAB SOUTH SLAB LINES IN PANEL PIECES
- DENOTES SUGGESTED SLAB CUT LOCATIONS FOR REMOVAL IN PANELS
- DENOTES BEAM TO COLUMN CUT LINES - CUT AFTER SLAB HAS BEEN REMOVED
- DENOTES BEAM TO COLUMN CUT LINES - CUT AFTER SLAB HAS BEEN REMOVED



16 LEVEL 1 MEZZANINE DEMO
3/16" = 1'-0"

KEYNOTES

02-02	REMOVE AND LEGALLY DISPOSE OF EXISTING (CASEWORK,COUNTERTOP, SHELVING, ETC.) IN ITS ENTIRETY
02-03	REMOVE AND LEGALLY DISPOSE OF EXISTING WALL IN ITS ENTIRETY.
02-09	REMOVE AND LEGALLY DISPOSE OF EXISTING CARPET FLOORING AND BASE THROUGHOUT SPACE. PREPARE FLOOR SLAB FOR NEW FINISHES PER FINISH FLOOR PLAN
02-10	REMOVE AND LEGALLY DISPOSE OF EXISTING STAIR AND ASSOCIATED RAILING IN ITS ENTIRETY (PATCH AND REPAIR WALLS AND FLOORS AS REQUIRED TO COMPLETE NEW WORK)
02-11	REMOVE AND LEGALLY DISPOSE OF PORTION OF EXISTING FLOOR. VERIFY EXTENT OF DEMOLITION WITH NEW CONSTRUCTION PLANS.
02-42	REMOVE AND LEGALLY DISPOSE OF EXISTING MASONRY WALL IN ITS ENTIRETY.
02-43	REMOVE AND LEGALLY DISPOSE OF PORTION OF EXISTING MASONRY WALL. VERIFY EXTENT OF DEMOLITION WITH NEW CONSTRUCTION PLANS.
02-52	REMOVE AND LEGALLY DISPOSE OF EXISTING WINDOW SHADES, PATCH AND REPAIR EXISTING SUBSTRATE AS REQUIRED TO RECIEVE NEW FINISH.
02-57	DEMOLISH MEZZANINE LOW WALL AND WOOD PANELING CLOSING OFF INTERSTATIAL SPACE OF ADJACENT ROOM.

DEMOLITION LEGEND

- HATCH INDICATES ELEMENTS TO REMAIN
- HATCH INDICATES AREA NOT IN SCOPE OF WORK
- INDICATES BUILT ITEM TO BE REMOVED
- INDICATES LIGHT FIXTURE TO BE REMOVED

REF. MEP DEMOLITION DRAWINGS

DEMOLITION NOTES

1. *IT IS THE CONTRACTOR'S RESPONSIBILITY TO FAMILIARIZE HIMSELF/ HERSELF WITH THE SCOPE OF WORK.
2. THE DEMOLITION NOTES PROVIDE A GENERAL DESCRIPTION OF THE ITEMS AND AREAS REQUIRING REMOVAL. THE CONTRACTOR SHALL FIELD VERIFY ACTUAL QUANTITIES AND LOCATIONS OF ALL INDICATED ITEMS AS NECESSARY TO COMPLETE THE SCOPE OF WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
3. COORDINATE WITH OWNER FOR ANY EQUIPMENT TO BE SALVAGED. UNLESS SPECIFICALLY SCHEDULED FOR REUSE, DEMOLISHED MATERIALS SHALL BECOME THE POSSESSION OF THE CONTRACTOR AND SHALL BE IMMEDIATELY REMOVED FROM THE SITE.
4. REMOVE MATERIALS FROM SITE AND DISPOSE OF IN A LEGAL MANNER AT NO ADDITIONAL EXPENSE TO OWNER
5. DEBRIS FROM THE DEMOLITION SHALL NOT BE ALLOWED TO ACCUMULATE WITHIN THE BUILDING OR ON THE SITE.
6. REMOVE FROM SITE ANY CONTAMINATED, VERMIN INFESTED, OR DANGEROUS MATERIALS ENCOUNTERED AND DISPOSE OF BY SAFE MEANS SO AS NOT TO ENDANGER HEALTH OF WORKERS AND PUBLIC.
7. BURNING OF MATERIALS ON SITE IS NOT PERMITTED.
8. CLEAN-UP: MUST MEET GOVERNING DUST CONTROL CODES.
9. NOTIFY AFFECTED UTILITY COMPANIES BEFORE STARTING WORK AND COMPLY WITH THEIR REQUIREMENTS.
10. PREVENT MOVEMENT OR SETTLEMENT OF ADJACENT STRUCTURES. PROVIDE BRACING AND SHORING.
11. CARRY OUT DEMOLITION WORK TO CAUSE AS LITTLE INCONVENIENCE TO ANY ADJACENT OCCUPIED BUILDING OR SITE AS POSSIBLE AND WITH MINIMUM INTERFERENCE TO PUBLIC OR PRIVATE ACCESSES. MAINTAIN PROTECTED EGRESS AND ACCESS AT ALL TIMES.
12. CONTRACTOR SHALL PROVIDE TEMPORARY DUST AND CONSTRUCTION SEPARATION WALLS AS REQUIRED TO SHIELD THE PUBLIC FROM NOISE, DUST, WEATHER, AND OTHER HAZARDS THAT MAY BE EXPOSED AS A RESULT OF THE DEMOLITION WORK.
13. PERFORM CUTTING OF EXISTING CONCRETE AND MASONRY WITH SAWS AND CORE DRILLS. DO NOT USE JACK-HAMMERS EXCEPT WHERE PERMITTED BY OWNER.
14. BREAK CONCRETE AND MASONRY INTO SECTIONS LESS THAN 3 FEET IN ANY DIMENSION.
15. CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO INSURE EXISTING STRUCTURAL ELEMENTS REMAIN UNDAMAGED THROUGHOUT CONSTRUCTION. UNLESS SPECIFICALLY NOTED ON DEMOLITION PLAN. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO IDENTIFY AND PROVIDE ANY SHORING, BRACING, OR TEMPORARY STRUCTURE, AND TO COORDINATE WITH STRUCTURAL ENGINEER AS REQUIRED.
16. ALL PUBLIC UTILITIES TO REMAIN IN OPERATION THROUGHOUT CONSTRUCTION. CONTRACTOR TO COORDINATE ANY TEMPORARY SERVICES REQUIRED TO MAINTAIN BUSINESS OPERATIONS.
17. SEE ENGINEERING DRAWINGS FOR DUCTWORK, DIFFUSER, PLENUM BOX, ETC. DEMOLITION AND/OR PROTECTION.
18. FIRE SAFETY MUST BE MAINTAINED FOR ALL PERSONNEL WORKING ON THE FLOOR. ALL FIRE STAIRS, ALARMS, SPEAKERS, ETC. MUST REMAIN ACCESSIBLE AND OPERABLE AT ALL TIMES. CONTRACTOR SHALL MAKE NECESSARY PROVISIONS TO PROTECT THIS EQUIPMENT. IMMEDIATELY NOTIFY BUILDING SECURITY AND BUILDING MANAGER OF DAMAGED OR DISABLED SYSTEMS AND REPAIR OR REPLACE DAMAGED SYSTEMS IMMEDIATELY. RELOCATION OF SMOKE DETECTORS, PUBLIC ADDRESS SPEAKERS AND FIRE ALARM EQUIPMENT, NECESSITATED BY NEW CONSTRUCTION, SHALL BE ACCOMPLISHED AS A FIRST PRIORITY, AND PER THE PLANS.
19. IF ANY QUESTIONS ARISE AS TO THE REMOVAL OF ANY MATERIAL, CLARIFY THE POINT IN QUESTION WITH THE OWNER BEFORE PROCEEDING. IMMEDIATELY STOP WORK IF HAZARDOUS MATERIALS ARE FOUND AND CONTACT THE OWNER'S REPRESENTATIVE.
20. REMOVAL OF ANY EQUIPMENT, CABLING SWITCHES, AND CONDUIT PERTAINING TO DATA/COMMUNICATIONS AND TELEPHONE SHALL BE VERIFIED WITH TELEPHONE COMPANIES, SERVICE OWNER OR TENANT DATA/COMMUNICATIONS REPRESENTATIVE AS REQUIRED TO PREVENT NEW CONSTRUCTION DELAYS.
21. MAINTAIN EXISTING FIRE RATING OF ALL STAIR, ELEVATOR, AND MECHANICAL SHAFTS. REPAIR ANY DAMAGE OR PENETRATIONS IN RATED ASSEMBLIES TO CONFORM TO THEIR ORIGINAL LISTING REQUIREMENTS AND TO MAINTAIN FIRE PROTECTION AND SEPARATION AS ORIGINALLY DESIGNED.
22. AT COMPLETION OF DEMOLITION WORK, THE CONSTRUCTION AREA(S) SHALL BE LEFT IN "BROOM CLEAN" CONDITION. ALL DEBRIS AND MISCELLANEOUS MATERIAL SHALL BE REMOVED.
23. CONTRACTOR SHALL BE RESPONSIBLE FOR PATCHING AND/OR REPAIRING ANY DAMAGE CAUSED BY HIM OR HIS SUBCONTRACTORS. FINISH AS NECESSARY TO MATCH EXISTING ADJACENT FINISH, OR AS NOTED HEREIN.
24. FOR AREAS NOT IN DEMOLITION SCOPE OF WORK, PROTECT AS REQUIRED, ALL SURFACES, EQUIPMENT, FIXTURES AND HARDWARE DURING DEMOLITION AND/OR CONSTRUCTION.
25. PRIOR TO DEMOLITION, INVESTIGATE WALLS FOR CONCEALED PIPING AND INFORM OWNER/ARCHITECT OF ANY CONDITION NOT DOCUMENTED IN CONTRACT DRAWINGS. DEMO DESIGNATED WALL BASES, WALL FRAMING, BATT INSULATION AND GYPSUM BOARD. DEMO CONDUITS AND RECEPTACLES, REFERENCE ELECTRICAL DEMO PLAN FOR ADDITIONAL INFORMATION.
26. ALL EXISTING DIRECTIONAL SIGNAGE TO BE REMOVED UNLESS NOTED OTHERWISE.
27. WHERE NOTED, REMOVE FLOORING DOWN TO TOP OF CONC. SLAB, INCLUDING ADHESIVES, TRANSITION STRIPS, AND OTHER ASSOCIATED ELEMENTS, TYP., UNLESS NOTED OTHERWISE. PREPARE REMAINING SURFACES TO RECEIVE NEW FINISHES.
28. PRESERVE AND PROTECT ALL EXTERIOR WINDOWS AND SILLS UNLESS OTHERWISE NOTED THROUGHOUT CONSTRUCTION.
29. ANY SFRM THAT IS REMOVED OR DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED

sheet LEVEL 1 MEZZANINE DEMOLITION PLAN
project YELLOWSTONE COUNTY COURTHOUSE
owner YELLOWSTONE COUNTY

project # 24104

No.	Description	Date
1	PERMIT CORRECTIONS	02/06/2026
2	BULLETIN #1	08/14/2026
3	BULLETIN #4	10.21.2026

phase
FINAL FOR CONSTRUCTION


issue date
06/11/2026

D2.1A

10/21/2026 3:10:07 PM

N. 3RD AVENUE

N. 27TH. STREET



KEYNOTES

11-02 SECURITY METAL DETECTOR WALK THRU & SECURITY TABLE; CONFIRM EQUIPMENT INSTALLATION / CLEARANCES; COORDINATE POWER ROUGH-IN. REF: ELECTRICAL DRAWINGS. OWNER PROVIDED, CONTRACTOR INSTALLED

FLOOR PLAN NOTES

1. REFER TO STRUCTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION. ALL INFORMATION REGARDING EXISTING CONDITIONS IS BASED UPON OWNER-SUPPLIED DOCUMENTS AND MAY NOT PRECISELY REFLECT FIELD CONDITIONS.
2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSPECT AND ASSESS EACH AREA OF WORK. DISCREPANCIES SHALL BE BROUGHT TO THE DESIGN TEAMS ATTENTION FOR FURTHER COORDINATION.
3. FIELD VERIFY ALL DIMENSIONS. DO NOT SCALE DRAWINGS.
4. ALL FINISHES AND MATERIALS SHALL BE PROPERLY INTEGRATED TO ENSURE A UNIFORM APPEARANCE AND SEAMLESS TRANSITION.
5. PROVIDE ALL BACKING FOR MILLWORK, GRAB BARS, AND ANY AND ALL WALL MOUNTED EQUIPMENT OR ACCESSORIES; COORDINATE LOCATIONS.
6. ALL DIMENSIONS ARE FROM STRUCTURAL OR UNFINISHED FACE OF STUD, UNLESS OTHERWISE NOTED.
7. GENERAL CONTRACTOR SHALL COORDINATE ALL ASPECTS OF THE BUILDING CONSTRUCTION.
8. PROVIDE A SMOOTH AND LEVEL FINISH FLOOR, TYP. PATCH AND REPAIR ALL INCONSISTENCIES IN FLOOR ELEVATIONS. REF. INTERIOR DETAILS FOR REQUIRED FLOOR TRANSITIONS
9. PATCH AND REPAIR ANY / ALL WALL SURFACES AS REQUIRED TO PROVIDE SUITABLE SUBSTRATE FOR FINISHES.
10. U.L. ASSEMBLIES DESCRIBED ARE FOR REFERENCE ONLY. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ENSURING A CONTIGUOUS RATED ASSEMBLY.
11. REFER TO DOOR AND FRAME SCHEDULE FOR DOORS REQUIRING ADA ACCESS CONTROL.
12. LOCATE THE HINGE SIDE JAMB OF DOORS 4" FROM ADJACENT PERPENDICULAR WALL, UNLESS NOTED OTHERWISE.
13. PROVIDE ACOUSTICAL SEALANT AROUND ALL NEW FRAMED PARTITIONS AND AT THROUGH WALL PENETRATIONS, INSTALL PUTTY PADS AROUND ELECTRICAL BOXES WHERE PARTITION CONTAINS ACOUSTICAL INSULATION.
14. REFER TO SPECIFICATIONS FOR CODE REQUIRED SIGNAGE. PROVIDE ADDITIONAL SIGNAGE AS MAY BE REQUIRED BY REQUEST OF THE FIRE MARSHAL AND/OR BUILDING CODE OFFICIAL.

REMODEL LEGEND

HATCH INDICATES EXISTING ELEMENTS TO REMAIN

sheet LEVEL 1 FLOOR PLAN
project YELLOWSTONE COUNTY COURTHOUSE
owner YELLOWSTONE COUNTY

project # 24104

No.	Description	Date
1	PERMIT CORRECTIONS	02/06/2026
2	PERMIT CORRECTIONS #2	03/03/2026
3	ADDENDUM #1	03/20/2026
4	ADDENDUM #3	04/27/2026
5	BULLETIN #1	08/14/2026
6	BULLETIN #2	09/03/2026
7	BULLETIN #4	10.21.2026


phase
FINAL FOR CONSTRUCTION

issue date
06/11/2026

A2.1

16 LEVEL 1_ FLOOR PLAN
3/16" = 1'-0"

10/21/2026 3:10:11 PM



KEYNOTES

11-02 SECURITY METAL DETECTOR WALK THRU & SECURITY TABLE: CONFIRM EQUIPMENT INSTALLATION / CLEARANCES; COORDINATE POWER ROUGH-IN, REF. ELECTRICAL DRAWINGS. OWNER PROVIDED, CONTRACTOR INSTALLED

32-01

FLOOR PLAN NOTES

1. REFER TO STRUCTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION. ALL INFORMATION REGARDING EXISTING CONDITIONS IS BASED UPON OWNER-SUPPLIED DOCUMENTS AND MAY NOT PRECISELY REFLECT FIELD CONDITIONS.
2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO INSPECT AND ASSESS EACH AREA OF WORK. DISCREPANCIES SHALL BE BROUGHT TO THE DESIGN TEAMS ATTENTION FOR FURTHER COORDINATION.
3. FIELD VERIFY ALL DIMENSIONS. DO NOT SCALE DRAWINGS.
4. ALL FINISHES AND MATERIALS SHALL BE PROPERLY INTEGRATED TO ENSURE A UNIFORM APPEARANCE AND SEAMLESS TRANSITION.
5. PROVIDE ALL BACKING FOR MILLWORK, GRAB BARS, AND ANY AND ALL WALL MOUNTED EQUIPMENT OR ACCESSORIES; COORDINATE LOCATIONS.
6. ALL DIMENSIONS ARE FROM STRUCTURAL OR UNFINISHED FACE OF STUD, UNLESS OTHERWISE NOTED.
7. GENERAL CONTRACTOR SHALL COORDINATE ALL ASPECTS OF THE BUILDING CONSTRUCTION.
8. PROVIDE A SMOOTH AND LEVEL FINISH FLOOR, TYP. PATCH AND REPAIR ALL INCONSISTENCIES IN FLOOR ELEVATIONS. REF. INTERIOR DETAILS FOR REQUIRED FLOOR TRANSITIONS
9. PATCH AND REPAIR ANY / ALL WALL SURFACES AS REQUIRED TO PROVIDE SUITABLE SUBSTRATE FOR FINISHES.
10. U.L. ASSEMBLIES DESCRIBED ARE FOR REFERENCE ONLY. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ENSURING A CONTIGUOUS RATED ASSEMBLY.
11. REFER TO DOOR AND FRAME SCHEDULE FOR DOORS REQUIRING ADA ACCESS CONTROL.
12. LOCATE THE HINGE SIDE JAMB OF DOORS 4" FROM ADJACENT PERPENDICULAR WALL, UNLESS NOTED OTHERWISE.
13. PROVIDE ACOUSTICAL SEALANT AROUND ALL NEW FRAMED PARTITIONS AND AT THROUGH WALL PENETRATIONS, INSTALL PUTTY PADS AROUND ELECTRICAL BOXES WHERE PARTITION CONTAINS ACOUSTICAL INSULATION.
14. REFER TO SPECIFICATIONS FOR CODE REQUIRED SIGNAGE. PROVIDE ADDITIONAL SIGNAGE AS MAY BE REQUIRED BY REQUEST OF THE FIRE MARSHAL AND/OR BUILDING CODE OFFICIAL.

REMODEL LEGEND

HATCH INDICATES EXISTING ELEMENTS TO REMAIN

15 LEVEL 1_DIMENSION FLOORPLAN
3/16" = 1'-0"

SCALE: 3/16" = 1'-0"

NORTH

10/21/2026 3:10:13 PM

sheet LEVEL 1 DIMENSION PLAN
project YELLOWSTONE COUNTY COURTHOUSE
owner YELLOWSTONE COUNTY


project # 24104

No.	Description	Date
1	PERMIT CORRECTIONS	02/06/2026
2	PERMIT CORRECTIONS #2	03/03/2026
3	BULLETIN #1	08/14/2026
4	BULLETIN #2	09/03/2026
5	BULLETIN #4	10.21.2026


phase
FINAL FOR CONSTRUCTION

issue date
06/11/2026


A2.1D




1 101A COURTROOM 1 - N
1/4" = 1'-0"




3 101A COURTROOM 1 - E
1/4" = 1'-0"




6 101A COURTROOM 1 - S
1/4" = 1'-0"



8 101A COURTROOM 1 - W
1/4" = 1'-0"



16 101A COURTROOM 1 - NW
1/4" = 1'-0"



17 ENLARGED PLAN - 101A COURTROOM 1
1/4" = 1'-0"

ENLARGED PLANS & ELEVATIONS GENERAL NOTES

1. REFER TO A300 SERIES SHEETS FOR WALL TAGS, DOOR TAGS, WINDOW TAGS, ADDITIONAL DIMENSIONS AND OVERALL FLOOR PLANS.
2. REFER TO G3.0 ACCESSIBILITY SHEET FOR TYPICAL MOUNTING HEIGHTS LEGEND.
3. REFER TO THE FINISH MATERIAL LEGEND AND SPECIFICATIONS FOR MATERIAL INFORMATION.
4. REFER TO REFLECTED CEILING PLANS FOR CEILING HEIGHTS AND TYPES.
5. REFER TO FLOOR FINISH PLANS FOR FLOOR FINISH MATERIALS.
6. FOR ANY WALL MOUNTED ITEMS NOT SHOWN ON ELEVATIONS; COORDINATE WITH ARCHITECT PRIOR TO INSTALL.
7. REFER TO FLOOR PLANS FOR EXACT WINDOW LOCATION AND WALL DIMENSION.
8. MILLWORK CONTRACTOR TO CONFIRM ALL FINISHED OPENING SIZES OF EQUIPMENT AND APPLIANCES WITH MANUFACTURER.
9. PROVIDE BLOCKING IN WALLS BEHIND ALL WALL HUNG ELEMENTS, INCLUDING BUT NOT LIMITED TO, LARGE SIGNAGE, COUNTER AND COUNTER SUPPORTS, CASEWORK, TVS, DOOR STOPS, ETC. WHETHER PROVIDED BY CONTRACTOR OR OWNER.
10. DEVICES, EQUIPMENT, AND FIXTURES SHOWN FOR LOCATION COORDINATION. REFER TO STRUCTURAL, ELECTRICAL, MECHANICAL, PLUMBING AND ALL OTHER CONSULTANT DRAWINGS FOR DETAILS AND ADDITIONAL WORK.
11. CASEWORK SCRIBES AND FILLER PANELS REQUIRED AT ALL ADJACENT WALLS AND EQUIPMENT, INCLUDING BASE, FULL HEIGHT AND UPPER CABINETS.
12. REFER TO SIGNAGE SCHEDULE FOR TYPICAL ADA SIGNS AND GRAPHICS.
13. AT ALL TILE LOCATIONS, USE CEMENTITIOUS BACKER BOARD, TYP.
14. FURNITURE LAYOUT IS FOR REFERENCE ONLY, FURNITURE IS BY OWNER
15. COORDINATE ALL CEILING & WALL MOUNTED DEVICE TRIMS/FRAMES TO MATCH ADJACENT FINISHES. APPLIES TO, BUT NOT LIMITED TO: GRILLES, LIGHT TRIMS, ACCESS PANELS, SENSORS, SPRINKLES AND SIMILAR ELEMENTS.
    - A. USE A WHITE FINISH AT WHITE PAINTED CEILINGS / WALLS
    - B. PROVIDE COLOR-MATCHED FINISHES AT WOOD CEILINGS / WALLS AND OTHER SPECIALTY FINISHES
    - C. SUBMIT PHYSICAL SAMPLE TO DESIGNER PRIOR TO ORDERING / INSTALLING

KEYNOTES


02-54	DASHED LINES INDICATE EXISTING WINDOW BEHIND NEW CONSTRUCTION.
08-02	GLAZING PRIVACY FILM, REF. A9.1 SHEET DOOR SCHEDULES FOR MORE INFORMATION
11-03	FURNITURE & EQUIPMENT BY OWNER; COORDINATE WITH OWNER FOR FINAL LOCATION. VERIFY DIMENSIONS PRIOR TO INSTALLATION

REMODEL LEGEND


HATCH INDICATES EXISTING ELEMENTS TO REMAIN

CASEWORK LEGEND

CASEWORK TYPE SYMBOL:



CASEWORK TYPE MODIFIERS ARE INDICATED IN THE NUMBER AND A DESCRIPTION; SEE BELOW.



CUSTOM CASEWORK IS INDICATED IN THE TYPE NUMBER FIELD AND ACCOMPANIED WITH DETAILS SHOWN ON ELEVATIONS; SEE BELOW.



THE **CDS IS SUBDIVIDED AS FOLLOWS**:

BASE CABINETS W/O DRAWERS	100 SERIES
BASE CABINETS W/ DRAWERS	200 SERIES
WALL-HUNG CABINETS	300 SERIES
TALL STORAGE CABINETS	400 SERIES
TALL WARDROBE CABINETS	500 SERIES
LIBRARY CABINETS	600 SERIES
MOVABLE CABINETS	700 SERIES

EXAMPLE:

GENERAL NOTES: (REFER TO AWS APPENDIX A FOR TYPE DESCRIPTIONS)

1. 100 OR 200 SERIES CABINETS MAY BE CONVERTED INTO MOVEABLE CABINETS BY PREFIXING A"T"TO THE NUMBER. (EXAMPLE: T-102- 36"x30"x18 [T-102-914 mm x 762 mm x 457 mm]).
2. MOVEABLE CABINETS SHALL BE EQUIPPED WITH ADEQUATE APPROVED CASTERS FOR THE INTENDED LOAD CAPACITY.
3. CDS #'s 728, 729, 735, 736, 737, 738, AND 739 REQUIRE METAL ANGLE REINFORCED CORNERS.
4. CARTS AND ROLLING TALL STORAGE CABINETS WITH DOORS, LACKING ANY HORIZONTAL; AND/OR VERTICAL STABILIZING DIVIDERS, REQUIRE A DIAPHRAGM BOTTOM, SPECIFICALLY CDS #'S 702, 712, 716, 722, 743,744, 746, 747, 50, AND 751.
5. WARDROBE CABINETS (500 SERIES) WITH DOORS REQUIRE A FRAMED MIRROR AND ONE DOOR, AND CABINETS # 533 AND 534 REQUIRE A PAPER ROLLER/CUTTER AND SLIDE-OUT TILTING PAPER SHELVES.
6. CART STORAGE CABINETS ARE REQUIRED TO HAVE HARDWOOD SIDE GUIDES, SPECIFICALLY CDS #'s 160, 161, AND 182.
7. CERAMICS DRYING CABINETS ARE REQUIRED TO HAVE GALVANIZED METAL FRAME SHELVES WITH WIRE MESH, SPECIFICALLY CDS #'s 198 199, AND 459.
8. FILE DRAWERS REQUIRE FULL-EXTENSION SLIDES AND A FILE-HANGING SYSTEM, SPECIFICALLY CDS #'s 223, 224, 230, 231, 240, 242, 253, 255, 531, 532, AND 533.
9. WARDROBE CABINETS ARE REQUIRED TO HAVE A SHELF, POLE, AND FRAMED MIRROR WHEN CLOSED WITH HINGED DOORS, SPECIFICALLY, CDS #'s 501, 511, 512, 522, 530, 531, 532, AND 552.
10. HD SUPPORT BRACKETS ALIGN WITH STUD FRAMING 32" O.C MAX SPACING

sheet ENLARGED PLANS & ELEVATIONS - 101 COURTROOM
project YELLOWSTONE COUNTY COURTHOUSE
owner YELLOWSTONE COUNTY

project # 24104

No.	Description	Date
1	PERMIT CORRECTIONS	02/06/2026
2	PERMIT CORRECTIONS #2	03/03/2026
3	ADDENDUM #1	03/20/2026
4	ADDENDUM #2	03/26/2026
5	ADDENDUM #3	04/27/2026
6	ADDENDUM #4	05/08/2026
7	BULLETIN #4	10.21.2026

phase
FINAL FOR CONSTRUCTION

issue date
06/11/2026

A3.1

10/21/2026 3:10:16 PM



16 LEVEL 1 RCP
3/16" = 1'-0"

KEYNOTES

12-03	CEILING MOUNTED ROLLER SHADE; REF. FINISH LEGEND AND SPECS FOR MORE INFORMATION
12-04	INSIDE WINDOW FRAME MOUNTED ROLLER SHADE; REF. FINISH LEGEND & SPECS FOR MORE INFORMATION

RCP NOTES

1. REFER TO ELECTRICAL SHEETS FOR FIXTURE TYPES, SWITCHING, AND SPECIAL SYSTEMS.
2. REFER TO MECHANICAL SHEETS FOR DIFFUSER AND DUCTING LAYOUTS.
3. REFERENCE EXTERIOR FINISH LEGEND FOR EXTERIOR PAINT COLORS; REFERENCE FINISH SCHEDULE FOR INTERIOR PAINT COLORS AND FINISH.
4. CEILING HEIGHTS ARE IN REFERENCE TO "ABOVE FINISH FLOOR" BELOW. (A.F.F.)

RCP LEGEND

- 2x2 LIGHT FIXTURE
- 2x4 LIGHT FIXTURE
- STRIP LIGHT FIXTURE
- 6" RECESSED CAN LIGHT FIXTURE
- SUPPLY AIR DIFFUSER
- RETURN AIR VENT
- EXHAUST FAN
- RECESSED LINEAR LIGHT FIXTURE (LENGTH VARY, REF LIGHTING SCHEDULE)

CEILING FINISH MATERIAL LEGEND

- EX. — EXISTING CEILING
- GYP-1 — GYP CEILING
- SCLG-1 — WOOD CEILING
- APC-1 — ACOUSTIC CEILING TILE 2X4
- APC-2 — ACOUSTIC CEILING TILE DECORATIVE
- PNLG-1 — PNLG SOFFIT
- SOF-1 — EXTERIOR METAL SOFFIT
- HATCH INDICATES SOUND BATT INSULATION OVER TOP OF CEILING SYSTEM

sheet LEVEL 1 REFLECTED CEILING PLAN
project YELLOWSTONE COUNTY COURTHOUSE
owner YELLOWSTONE COUNTY

project # 24104

No.	Description	Date
1	PERMIT CORRECTIONS	02/06/2026
2	ADDENDUM #4	05/08/2026
3	BULLETIN #1	08/14/2026
4	BULLETIN #2	09/03/2026
5	BULLETIN #4	10.21.2026

phase
FINAL FOR CONSTRUCTION

issue date
06/11/2026

A7.1

10/21/2026 3:15:57 PM

Outlook

24104 YCCH

From Adam Baumgartner <abaumgartner@ae.design>
Date Fri 10/16/2026 11:14 AM
To Brooke Logan <blogan@sletteninc.com>; Alec Pinero <alecp@hccm-inc.com>; Robby Carmody <rcarmody@ae.design>; kyle.j.blankenship <kyle.j.blankenship@imegcorp.com>; Brianna Kessler <bkirkeeng@ae.design>; Matt Krivonen <matt@krivonen.com>; clint.e.laferriere <clint.e.laferriere@imegcorp.com>; Cady Marjerison <cmarjerison@ae.design>
Cc Jeanne M. Walker <jmwalker@yellowstonecountymt.gov>; David Carter <dacarter@yellowstonecountymt.gov>

1 attachment (6 MB)
24104 YCCH MM_10.16.2026.pdf;

[CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe]

YCCH Team,

We walked the courthouse main level with Judges Walker and Carter yesterday to review the courtrooms and office areas. They requested several changes, and we identified additional coordination and code-related items. The items needing to be addresses are listed below and shown on the attached plans and RCP's.

Krivonen, please review the feasibility of removing the mezzanine above the closet in NW courtroom.

Please plan to discuss the following during Monday's OAC at 1:00 p.m. IMEG, please have someone available to review the mechanical, electrical, and plumbing items.

Courtroom 101A

- Modify the ceiling design per the attached markup.
- Move the witness stand as far north as possible to provide more space at the judge's desk.
- Provide power and data at the podiums.
- Provide a destratification fan. This room may regularly accommodate 30–40 people.

Transaction Lobby 102

- Make all three transaction windows along the south wall standard height; an accessible-height window is not needed along this wall.

Hall 103

- Relocate the pipes near the column at Grid 7/C to maintain the required 44-inch clear exit path between the wall and column.

Clerk Work Area 104

- Raise the outlets on the east and west walls to 60 inches above finished floor.

Clerk Open Office 110

- Review power capacity and outlet distribution along the south wall serving the four-desk groups. Currently, there appears to be only one 20-amp receptacle for every four desks. Each desk will have a computer with dual monitors, a scanner, and at least one additional appliance.
- Maximize desktop space by removing the tall cabinet and providing storage below the desktop.
- Relocate the standpipe at the column at Grid 7/E. We did not get a photo of this condition.

Courtroom 112A

- Demolish the walls enclosing Storage 114 and the mezzanine above, and use this area for the jury box.
- Provide power and data at the podiums.

Thanks,

ADAM BAUMGARTNER
AIA
architect | associate principal

o 406 248 2633

A&E + SMA Design
124 N. 29th St, Ste. 100
Billings, MT 59101

ae-sma.design

Different by Design. Driven to Create Impact.

	JUDGE WALK COST ELEMENTS:	
	DESCRIPTION	**RANGE OF MAGNITUDE COST**
	COURTROOM 112A	
1	DEMO OF MEZZANINE AND DISPOSE (INCLUDES DUMP/CLEAN-UP)	$ 20,000.00
2	ADDITION OF WALL FOR STRUCTURAL SUPPORT AT MEZZANINE BEAM	$ 8,500.00
3	STRUCTURAL STEEL - ANGLES/BOLTS/INSTALL	$ 4,500.00
4	HANG/TAPE & PAINT - PATCHING AND PAINTING ALLOWANCE	$ 4,500.00
5	LIGHTING MODIFICATIONS AT JURY BOX	$ 3,500.00
6	ADDED FLOORING AT JURY BOX & FLATTENING/PREP	$ 7,500.00
7	RECONFIGURE OF JURY BOX	$ 5,000.00
	COURTROOM 101A	
1	DESTRATIFICATION FAN & INSTALL	$ 15,000.00
2	REMOVE SOFFIT FOR RAISING OF CEILING	$ 2,000.00
3	ADDED FINISHES - WHERE WALL WILL NOW BE FINISHED TO CAPTURE WINDOW	$ 5,000.00
4	RAISE CEILING IN JURY SUITE 103A - ADDED FINISHES AT THE EAST WELL	$ 7,500.00
5	RECONFIGURE OF JURY SEATING - ADDD PONY WALLS/WALL PANELING	$ 6,500.00
6	EXPANSION OF THE JUDGE BENCH/PLATFORM	$ 6,500.00
7	CHANGE PLATFORM FOR THE JURY LAYOUT REVISIONS	$ 5,000.00
	ADDITION OF OUTLETS IN CLERK AREA	
1	DOUBLE OF THE AMOUNT OF OUTLETS AT THE SOUTH WALL	$ 12,000.00
AA	CONTINGENCY FOR THIS SCOPE 25%	$ 28,250.00
	SUBTOTAL:	**$ 141,250.00**
A	GENERAL REQUIREMENTS	$ 11,300.00
B	INSURANCE	$ 991.58
C	BONDING	$ 1,535.42
D	MARK-UP	$ 7,333.08
E	1% GRT	$ 1,624.10
	OVERALL TOTAL:	**$ 164,034.17**

SCHEDULE TIME TO ADD TO THE DURATION OF THE PROJECT

1	STANDBY TIME	3 WEEKS
2	DESIGN	3 WEEKS
3	IMPLEMENT SCOPE ITEMS - DEMOLITION	2 WEEKS
4	CONTINGENCY	2 WEEKS
	TOTAL NUMBER OF WEEKS	**10 WEEKS**

B.O.C.C Thursday Discussion 2. b.

Meeting Date: 11/05/2026

Title: Sletten-Courthouse Renovation Flooring Carpet vs. L.V.T.

Submitted By: Jared Gavin

TOPIC:

Sletten-Courthouse Renovation Flooring Carpet vs. L.V.T.

BACKGROUND:

Sletten is requesting to discuss the different flooring options for the Courthouse Renovation. Information included in the attachments is a memo from A&E Design regarding the noise reduction with carpet vs. L.V.T. The price to switch to L.V.T. flooring is $148,703.87.

RECOMMENDED ACTION:

Sign and approve a copy to Finance

Attachments

A&E Design Memo

ROM Carpet Option to LVT

Courtroom Flooring Recommendation

DATE: October 30, 2026

TO: Yellowstone County Commissioners

FROM: Adam Baumgartner, Associate Principal, A&E+SMA design

RE: Retaining specified carpet in the courtrooms

We recommend retaining the specified carpet in the courtroom renovations. Clear speech and a quiet environment are essential to courtroom operations, and the floor finish contributes directly to both.

Carpet reduces noise from footsteps, moving chairs, and dropped objects. It also absorbs a portion of the sound that would otherwise reflect back into the room. LVT and exposed concrete provide substantially less sound absorption and allow everyday movement to become more disruptive during testimony and proceedings.

Replacing carpet with a hard surface would increase sound reflections and could make speech harder to understand, depending on the other finishes in the room. This affects judges, jurors, attorneys, witnesses, and the courtroom recording system. Acoustic ceilings and wall treatments help control reflected sound, but they do not prevent footfall and chair noise at its source as carpet does.

Although hard flooring may offer maintenance advantages, it is not an acoustically equivalent substitution. Any initial savings should be weighed against potential additional acoustic treatments and the ongoing impact on courtroom use.

Our recommendation is to retain the specified carpet. If a hard floor remains under consideration, the change should first receive an acoustic review to identify necessary compensating measures and their cost.

Adam Baumgartner
Associate Principal
A&E+SMA design

	JUDGE WALK COST ELEMENTS:	
	DESCRIPTION	**RANGE OF MAGNITUDE COST**
	UPDATE FROM CARPET TO LVT ON 1,2,3	
1	CHANGE FROM CARPETING PRODUCT TO LVT PRODUCT THROUGHOUT THE SPACES * INCLUDES FLATTENING OF ALL 3 FLOORS	$ 120,234.94
	****NO CHANGE TO CPT 3 - WALK OFF CARPETING; CPT-4 - CUSTOM CARPET LOGO**	
AA	CONTINGENCY FOR THIS SCOPE 7%	$ 8,416.45
	SUBTOTAL:	**$ 128,651.39**
A	GENERAL REQUIREMENTS	$ 10,292.11
B	INSURANCE	$ 903.13
C	BONDING	$ 1,398.47
D	MARK-UP - 4%	$ 5,986.46
E	1% GRT	$ 1,472.32
	OVERALL TOTAL:	**$ 148,703.87**

SCHEDULE TIME TO ADD TO THE DURATION OF THE PROJECT

1	ADDED TIME FLOOR FLATTING (1 WEEK PER FLOOR)	3 WEEKS
2	LEAD TIME ON PRODUCT **CONTINGENT ON SELECTION OF STANDARD COLOR/PATTERN & AVAILABLE STOCK	4-6 WEEKS

FISCHER
COMMERCIAL FLOORING, LLC
802 Fourth Ave. North, Billings, MT 59101
fischercommercialflooring.com • 406-702-7070

Proposal 105037
11/03/2026

Customer
BROOKE LOGAN SLETTEN CONSTRUCTION-GREAT FAL 4801 RIVER DRIVE N GREAT FALLS, MT 059405

Project
YELLOWSTONE COUNTY COURTHOUSE CPT TO LVT W/LEVELLING COSTS 217 N 27TH ST. BILLINGS, MT 59101

Scope Of Work	Quantity	U/M	Labor	Material	Amount
LVT MOHAWK HOT & HEAVY II 5MM 20MIL 18X36 COLOR:TBD	27,216.00	SF	$96,056.47	$128,857.64	$224,914.11
LEVELING LEVELS 1-3 FOR LVT UZIN 170	624.00	EA	$39,929.40	$41,190.60	$81,120.00
(BASE BID) CPT-1 MOHAWK CONCRETE BLOOM 12X36 WILDWOOD DARK 868	-1,092.78	SY	($11,661.03)	($58,026.50)	($69,687.53)
(BASE BID) CPT-2 MOHAWK CELEBRATED HERITAGE II WOVEN TRADITIONS 12X36 BITTER CHERRY 829	-1,036.74	SY	($11,011.93)	($41,672.23)	($52,684.16)
(2ND FLOOR) CPT-1 MOHAWK CONCRETE BLOOM 12X36 WILDWOOD DARK 868	-135.43	SY	($1,373.04)	($7,414.45)	($8,787.49)
(2ND FLOOR)CPT-2 MOHAWK CELEBRATED HERITAGE II WOVEN TRADITIONS 12X36 BITTER CHERRY 829	-700.50	SY	($7,005.00)	($29,175.25)	($36,180.25)
(DA OFFICES)CPT-2 MOHAWK CELEBRATED HERITAGE II WOVEN TRADITIONS 12X36 BITTER CHERRY 829	-350.25	SY	($4,378.12)	($14,081.62)	($18,459.74)

Grand Total **$120,234.94**

QUOTE FOR REPLACING ALL CPT-1 & CPT-2 FOR LVT

QUOTE INCLUDES ALLOWANCE OF ADDITIONAL FLOOR PREP THAT WILL BE NEEDED WITH INSTALLTION OF LVT VS CPT FIGURED AT $130 PER BAG FIGURED FOR 3/16"

LVT QUOTED USING MOHAWK HOT & HEAVY COLLECTION

QUOTE DOES NOT INCLUDE ANY CHANGE FOR CPT-3 (WALK OFF CPT) OR CPT-4 (CUSTOM CARPET LOGO)

Terms & Conditions

GUARANTEES: Contractor agrees to guarantee its workmanship for a period of one (1) year from the date of completion of the work. The contractor shall remove, replace, and/ or repair at its own expense its defective workmanship at any time within a period of one (1) year after completion of the work. Material warranties are provided by the manufacturers. Contractor does not manufacture material or guarantee it. Contractor will assist Owner in getting resolution on material claims, if necessary.

MANUFACTURER REQUIREMENTS
The Contractor will install all materials according to the manufacturer's installation instructions. Installation instructions often include specifications such as required ambient and/or substrate temperature and relative humidity values. Should job site conditions not meet manufacturer requirements, the Contractor will not start (or continue, if already in-work) the installation process until these requirements are met. Installation of materials outside of the manufacturer's requirements can void the manufacturer's warranty.

GENERAL: 1. Material and workmanship to meet the codes and requirements of all appropriate governmental authorities. 2.
All work to be done in a neat and workmanlike manner. Contractor agrees to leave a workplace clean and orderly upon completion of both rough and finish work. All debris will be removed from the premises.

CHANGES: No changes to the scope of the work will be effective without a written change order signed by both the
Contractor and Owner. Any changes to job site conditions or material selections, which affect Contractor's material usage, add labor costs, shipping costs, etc. will be an extra charge and will be executed in writing.

PAYMENTS: Contractor shall make application for payment to Owner once per month for the work completed in the prior month. Owner must make payment to Contractor within twenty-one (21) days of receipt of the application for payment.
Unpaid payment applications will accrue interest at the rate of twelve (12) percent per year. In addition, Owner is responsible for all costs of collecting unpaid payment applications, including legal fees.
*Payments made by credit card will incur a processing fee of 2.40%.

ENTIRE CONTRACT: This agreement contains all the terms, conditions, agreements, representations, and warranties agreed upon by the parties to this agreement relating to the subject of this agreement and supersede all prior agreements, negotiations, correspondence, understandings, undertakings, and communication of the parties, whether oral or written, respecting such subject matter. All parties acknowledge that he, she, or it has an opportunity to assist in the drafting of this agreement. Accordingly, the agreement should not be interpreted against any one party or draftsman.

GOVERNING LAW: This agreement shall be governed by, and interpreted and enforced in accordance with, the laws of the
State of Montana and of the United States of America. The parties agree that Montana's Prompt Payment Act applies to this agreement.

SEVERABILITY: If any term, condition, agreement or other provision of this agreement, or the application thereof to any party or circumstances, shall be held to be invalid or unenforceable to any extent in any jurisdiction, then the remainder of this agreement and the application such term, condition, agreement, or other provision in any other jurisdiction or to persons or circumstances other than those as to whom or which it is held invalid or unenforceable, shall not be affected thereby, and each term, condition, agreement and other provision of this agreement shall be valid and enforceable to the fullest extent permitted by law.

DISPUTE RESOLUTION INCLUDING ARBITRATION: Any dispute between the parties concerning the interpretation of enforcement or this agreement must be settled by arbitration before a single arbitrator. Before pursuing arbitration, however, the parties must attempt negotiation and mediation. Mediation shall be done before a mediator is chosen by the parties. If they cannot agree on a mediator, then they each shall choose a legal representative and the two representatives shall agree on a mediator. If the parties cannot resolve their dispute by negotiation or mediation, they will proceed to arbitration. The arbitration must take place in the county in which the subject of the contract work is located. The parties to the arbitration will be entitled to conduct discovery in accordance with the Federal Rules of Civil procedure, subject to limitation by the arbitrator to secure just and efficient resolution of the dispute. The arbitration shall be done before a single arbitrator is chosen by the parties. If the parties cannot agree on the arbitrator, then they shall each choose a legal representative and the two representatives shall agree on an arbitrator. If the amount in controversy exceeds $10,000, the arbitrator's decision must include a statement specifying in reasonable detail the basis for and computation of the amount of the award, if any. Each party to the mediation and/or arbitration shall bear its own costs and fees as well as one half of the cost of the mediator and/or arbitrator, however, a party substantially prevailing in the arbitration will also be entitled to recover such amount for its costs and attorney fees incurred in connection with the mediation and/or arbitration as may be determined by the arbitrator. Judgement upon the arbitration award may be entered in any court having jurisdiction. Nothing contained in this section, however, will prevent a party from seeking relief in a court having jurisdiction in situations in which injunctive relief may be appropriate. Also, nothing here in prevents the Contractor from filing a construction lien as permitted by Montana law.

Signature:		Signature:	
Name:	CORY SCHULZ	Authorized Agent:	
Title:	Salesperson	Title:	
Date:	11/3/2026	Date:	

B.O.C.C Thursday Discussion 1.

Meeting Date: 11/05/2026

Title: Board Recommendation

Submitted By: Erika Guy

TOPIC:

Board Recommendation - Michael Temporal to Allies in Aging

BACKGROUND:

See Attached. Recommended by the Allies in Aging Board

RECOMMENDED ACTION:

Discuss

Attachments

Michael Temporal

BOARD APPLICATION FORM
YELLOWSTONE COUNTY, MONTANA

NAME: Michael Temporal HOME PHONE: (406) 876-4634

ADDRESS: 717 Beartooth Circle WORK PHONE: (406) 238-2900

CITY: Laurel STATE: MT ZIP: 59044

BUSINESS OR JOB: Family Medicine / Geriatric Medicine Physician / Billings Clinic

E-MAIL ADDRESS: Mtemporal514@gmail.com

BOARD OR COMMISSION APPLIED FOR: Allies in Aging Board of Directors

Please describe your experience or background that you believe qualifies you for service on this Board or Commission (attach additional sheets if needed):

30yrs of clinical practice in primary care and geriatrics with focus on healthy aging and chronic disease management across the continuum from health and wellness to palliative care. Practice settings have included home visits, assisted living, nursing home and hospice care in addition to hospital and office setting. Have worked on the BOLD early diagnosis of dementia project, and previous board experience with Big Sky Senior Services Alzheimers Association of Montana.

Why do you wish to serve on this Board or Commission?

Help build programs and services that allow senior adults to thrive and maintain quality of life in the spirit of aging successfully. Provide medical perspective to the variety of solutions for maintaing seniors in their communities. I have a passion for working with elder citizens and finding solutions and advocating for older populations.

Additional information that you feel is pertinent (attach additional sheets if needed):

Following a family medicine residency, I completed a 2 year fellowship in geriatric medicine at UCLA. Experienced in comprehensive geriatric assessment and have worked with innovative community based programs including Program for All Inclusive Care (PACE), and continuing care retirement communities. I have led quality initiatives in delivering value based care, CMS programs including Medicare Advantage plans and Accountable Care Org



Signature 10/05/2026 Date

Return application to: Board of County Commissioners
P.O. Box 35000
Billings, MT 59107-5000

OFFICE USE ONLY:

APPOINTED: YES____ NO____ DATE _____

TERM EXPIRATION DATE: _____

(Circle one)

ORIGINAL APPOINTMENT REAPPOINTMENT TERM NO: _____